

#### Mahatma Gandhi Antarrashtriya Hindi Vishwavidyalaya, Wardha

Gandhi Hill, Wardha- 442001. (Maharashtra) [Phone No. 07152 - 232669] [Website: www.hindivishwa.org]

Tender No. MGAHV/CD/34/2018-19/04

**Tender Notice** 

Sealed tenders are invited for Providing & Fixing of Curb Stone, Paver Block, Fencing Jali and Development of Park infront of Professor Quarters, Transit Hostel, D-Quarters & C-Quarters. The tender should reach the University on or before 30.08.2018 up to 03:00 p.m.

The detailed terms and conditions of tender can be obtained from www.hindivishwa.org and www.eprocure.gov.in

Registrar

## MAHATMA GANDHI ANTARRASHTRIYA HINDI VISHWAVIDYALAYA

Post Hindi Vishwavidyalaya, Gandhi Hills, Wardha-442 001.

(Phone 07152-255686 Fax No 07152-247602) [Website: www.hindivishwa.org]

Tender No.: MGAHV/CD/34/2018-19/04

Date: 07.08.2018

File No.: 34/2015-16/वि.वि.प.सौ./33-1

# TENDER FOR CIVIL & FABRICATION WORK



TENDER FORM SALE WILL START FROM 10.00 AM on 08.08.2018

LAST DATE FOR SALE OF TENDER FORM : Upto 05.00 PM on 29.08.2018

LAST DATE FOR SUBMISSION OF TENDER FORM

Upto 03.00 PM on 30.08.2018

DATE OF OPENING OF TENDER (i.e. Technical Bid)

At 04.00 PM on 30.08.2018

Tender available on www.eprocure.gov.in & www.hindivishwa.org

TENDER FORM PRICE Rs. 500/-



## महात्मा गांधी अंतरराष्ट्रीय हिंदी विश्वविद्यालय, वर्धा

(संखद द्वारा पारित अधिनियम के अन्तर्गत स्थापित केन्सीय विश्वविद्यालय)

हिंदी विश्वविद्यालय, वर्धा - 442001 (महाराष्ट्र), बेबसाइट :www.hindivishwa.org

विश्वविद्यालय के दक्षिणी परिसर स्थित माननीय कुलपति एवं प्रतिकुलपति आवास के सामने, प्रोफेसर आवास (अङ्गेय संकुल), डी-क्वार्टर, ट्रांजिट हॉस्टल तथा सी-क्वार्टर के पास कर्ब स्टोन, पेवर ब्लॉक एवं फेनसिंग जाली लगाने का कार्य किया जाना है।

1 - कार्य का विवरण

- संलग्न

2- EMD যাগৈ ড. 50,000/-

मांगपत्र- वित्ताधिकारी म.गां.अं.हिं.वि..वर्घा, महाराष्ट्र के नाम देश।

- 3. जी.एस.टी. क्रमांक अनिवार्य ।
- 4. PAN क्रमांक अनिवार्य।
- सिवित एवं फैब्रिकेशन कार्य कराने का अनुभव प्रमाण पत्र जमा कराना अनिवार्य।
- 6. Technical & Financial bid अलग-अलग लिफाफे में जमा कराना अनिवार्य होगा।
- निविदा भरने से पूर्व कार्यस्थल का निरीक्षण करना अपेक्षित है। किसी भी प्रकार की जानकारी/स्पष्टीकरण परिसर विकास विभाग कार्यालय से प्राप्त किया जा सकता है।
- कायदिश जारी होने के पश्चात 60 दिनों में कार्य पूर्ण करना होगा।
- उक्त निविदा में संपूर्ण सामग्री, श्रमिक व्यय एवं कर आदि सिम्मिलित हैं।
- 10. श्रमिक का बीमा होना अनिवार्य।
- कार्य के दौरान यदि किसी प्रकार की दुर्घटना घटित होती हैं तो उसकी संपूर्ण जिम्मेदारी निविदाकारक की होगी।
- 12. कार्य के उपरान्त विश्वविद्यालय के अभियन्ताओं द्वारा संतोषजनक कार्य के प्रमाण पत्र के बाद ही भुगतान प्रक्रिया की जाएगी।
- 13. निविदा को कुलसचिव कार्यालय में रखे Tender Box में डालना होगा।
- 14. सभी अर्हताएँ निविदा जमा करने की तिथि को पूर्ण करना अनिवार्य है।
- 15. तकनीकी निविदा में सफल निविदाकारक को ई-मेल के माध्यम से सूचित किया जाएगा। जिससे तकनीकी निविदा में सफल समस्त निविदाकारक 'वित्तीय निविदा' खुलने के समय उपस्थित रह सकें।
- 16. निविदा प्रपत्र प्राप्त करने हेतु 'वित्ताधिकारी, म.गां.अं.हिं.वि., वर्घा (महाराष्ट्र)' के नाम से देय रू. 500/- (रू. पांच सो मात्र) का डिमांड ड्रापट परिसर विकास विभाग में जमा कर निविदा प्रपत्र प्राप्त किया जा सकता है। यदि निविदाकारक द्वारा वेबसाइट से निविदा प्रपत्र डाउनलोड कर निविदा जमा की जाती है तो उक्त निविदा प्रपत्र के साथ 'वित्ताधिकारी, म.गां.अं.हिं.वि., वर्घा (महाराष्ट्र)' के नाम से देय रू. 500/- का डिमांड ड्राप्ट जोइना अनिवार्य है।
- निविदा स्वीकार, अस्वीकार, निरस्त एवं विस्तारित करने का संपूर्ण अधिकार विश्वविद्यालय के पास सुरक्षित रहेगा।

टैंडर भरने वाले का हस्ताक्षर एवं मुहर

### Name of work : Providing and fixing of Curb Stone, Paver block, Fensing Jali at Professor Qtrs, Transit Hostel, D-Qtrs.

r. No.	Discription	Qty.	Rate	Amount
1	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead up to 50 m and lift up to 1.5 m:	54.64 cum.		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 Cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	65,25 cum.		
3	Providing and laying at or near ground level factory made curb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curb shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished curb edging shall be measured for payment). (Precast C.C. curb stone shall be approved by Engineer-in-charge).	196 cum.		
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer.			
5	Painting with synthetic enamel paint, having VOC (Volatile Organic Compound) content less than 150 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour with two coat	825. sq.m		

r. No.	Discription	Qty.	Rate	Amount
6	Providing & fixing M.S. Revolving gate 5 ft. height from ground level	2 Nos		
7	Muram Filling	19cum.		
8	Providing & Fixing fancing Jalli including material GI 50x50MM angle 12 Gauge 5 ft. height upto ground level	190 rmt.		
9	Providing & Fixing plastic Jalli including material for electric panel cover	20 sq.m.		
10	Providing & Fixing cement banch including necessary cement concrete base	6 Nos		
11	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement: 4 coarse sand) (for chamber work) (C-Qtrs, D-Qtrs. & Professor Qtrs.)	24.12 cum.		
12	Extra for plastering done on moulding cornices or architraves including neat finish to line and level: In two coats	160 .60 sq.m.		
13	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarses and filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	228 sq.m		
14	Providing and Spreading Bhashva Muram (450 Cu.ft.)	20 Tipper		
15	Providing and fixing electricity Pole with Solar Light including foundation (50 watt light)	04 Nos.		
	Total			

